

- 1-Phase Residential

Description	Milbank	(Talon) Siemens	Durham
125-135 amp, small	U7487-XL-TG-KK	UAT111-XPQG	RS-101, RS-111
200 amp, Duplex (2 meter)	U1252-X-KK	N/A	2R2332
200 amp, Residential	U7040-XL-TG-KK-ALT or U7040-XL-TG-KK	UAT417-XPQG	RS-213

- 1-Phase Commercial

Description	Milbank	(Talon) Siemens	Durham
200 amp, 4-terminal w/ lever bypass	U9801-RXL	40404-025	H4213
400 amp, 4-terminal w/ lever bypass	U1797-O-K3L-K2L or U2448-X	N/A	H4330 or H4336
600 amp, 4-terminal Bolt-in	U4664-X-8523	9810-9507	N/A

- 3-Phase Commercial

Description	Milbank	(Talon) Siemens	Durham
200 amp, 7-terminal w/ lever bypass	U9701-RXL-ALT or U9701-RXL	40407-025	H7213
400 amp, 7-terminal w/ lever bypass	U2594-X-K7-ALT or U2594-X	48707-02	H7330 or H7336-9
600 amp, 7-terminal Bolt-in	U4667-XT-9504	9817-9803	N/A

- AMES ELECTRIC SERVICES WILL CONTINUE TO SUPPLY CT-RATED SOCKETS AS THEY ARE COLOR CODED SPECIFICALLY FOR AMES ELECTRIC
- FOR INSTALLATIONS REQUIRING METER/DISCONNECT COMBOS, AMES ELECTRIC SERVICES WILL ACCEPT METER COMBOS ON THE APPROVED LIST FOR ALLIANT ENERGY
- CONTACT THE ELECTRIC METER DEPT (515-239-5510) WITH ANY QUESTIONS

<p style="text-align: center;">CITY OF AMES ELECTRIC SERVICES</p> <p>REVISED: MEI 8-17-2017</p> <p>APPROVED: MEI 8-17-2017</p>	<p style="font-size: 1.2em;">APPROVED LIST METER SOCKETS</p>	ELECTRIC METERING
		EM800
		PAGE 1 OF 1